



City of Niagara Falls

Addendum # 1

Contract #2018-471-18

Third Avenue Sewer and Watermain Replacement

This Addendum shall form an integral part of the contract document for the above noted project and shall be read in conjunction therewith. This Addendum shall, however, take precedence over all requirements of the previously issued contract documents, including plans, with which it may prove to be at variance, unless otherwise clarified by the Engineer.

This Addendum must be signed by the Tenderer in the appropriate space and must be attached to the Form of Tender for submission at the time of tendering. Tenders not including this Addendum, signed as required, may be rejected as informal.

No. of Addendum Pages: 3

No. of Attachments: 2

SPECIAL INSTRUCTIONS TO BIDDERS

1) Under Clause 14. Special Project Information

Replace the following:

This project is being undertaken as an emergency project and as such, is expected to be substantially completed by the date specified on page FT-2 in the 'Form of Tender' section.

with:

This project is being undertaken as an emergency project and as such, is expected to be substantially completed by the **dates** specified on page FT-2 in the 'Form of Tender' section.

FORM OF TENDER

- 1) Attached find a revised page FT-2 marked "Addendum#1 – Revised September 28, 2018" at the top of the page. **This revised page FT-2 shall replace FT-2 as originally provided and shall be submitted as part of the Form of Tender in Tender Envelope 2.**

The revised page FT-2 revises the commencement and completion clause from:

We agreed to commence work as specified to proceed continuously to the completion and to complete all the work at the unit prices tendered by **December 14, 2018**.

to:

We agree to commence work as specified to proceed continuously to the completion at the unit prices tendered by May 3, 2019 and, as a minimum, to complete all work under "Section 'C' Sewers", including all temporary restoration and ongoing seasonal maintenance at the unit prices tendered by December 14, 2018.

SPECIAL PROVISIONS – CONTRACT ITEMS SUPPLEMENTARY

1) Under Item C6. Precast Concrete Maintenance Holes, Catchbasins & Ditch Inlets,

Replace the following:

Inlet Control Devices (ICD)

Each catchbasin shall be fitted with a Framed Type 'A' Inlet Control Device, as supplied by IPEX, or an approved equivalent.

with:

Inlet Control Devices (ICD)

Each catchbasin shall be fitted with a ***Framed/Plate, Tempest MHF ICD Square Assembly with a 95mm round orifice***, as supplied by IPEX, or an approved equivalent.

SCHEDULE OF STANDARD DRAWINGS & SPECIFICATIONS

1) Under Clause 2. CITY OF NIAGARA FALLS STANDARD DRAWINGS

Add the following at the end of the table:

Description	Dwg. No.
<i>MHF Square CB Assembly</i>	<i>SGM74_FA007R01</i>

Date: September 28, 2018

Eric Lallouet
Project Manager

The Tenderer shall take due notice of this change and make allowance to his/her unit prices.

Signature of Company Representative:
Name (Please Print):
Company Name:
Date: