

All Bidders are to note that the Special Provisions - Contract Items Supplementary are regularly revised and in some cases modified to a specific project. The City will not be responsible for any Bidder not being aware of the changes from previous tender documents.

SCHEDULE OF QUANTITIES AND UNIT PRICES

CONTRACT NO. 2019-481-19

Chippawa West Stormwater Pond Landscape Development

ITEM NO.	SPEC NO.	DESCRIPTION	ESTIMATED QUANTITY	UNIT	UNIT PRICE	TOTAL PRICE
SECTION 'A' - GENERAL						
A1	A1	Bonding	1	L.S.	\$ _____	\$ _____
A4	SPCS	Construction Layout				
		a) Survey Layout	1	L.S.	\$ _____	\$ _____
		b) Progress and Final Record Photography	1	L.S.	\$ _____	\$ _____
		c) Digital Record Drawings	1	L.S.	\$ _____	\$ _____
A5	SPCS	Clearing and Grubbing				
		a) Remove Existing Trees, Brush, Shrus and Vegetation	1	L.S.	\$ _____	\$ _____
A7	SPCS	Install, Maintain and Remove Silt Control Devices				
		a) Light Duty Silt Fence Barrier, OPSD 219.110 (Provisional Item)	50	each	\$ _____	\$ _____
		b) Construction Fence/Hoarding, 1.8m high, Moduloc or approved substitute	25	lm	\$ _____	\$ _____
		c) Remove and dispose existing chain-link fence at Tallgrass Ave and Park	1	L.S.	\$ _____	\$ _____
A8	SPCS	Construction Signs, Traffic Control and Traffic Management Plan	1	L.S.	\$ _____	\$ _____
A9	SPCS	Contingency Allowance	1	L.S.	\$30,000.00	\$30,000.00

TOTAL SECTION 'A' - GENERAL \$

SECTION 'B' - PARK

B2	SPCS	Earth Excavation <i>Includes sawcutting and disposal of surplus or unsuitable excavated materials</i>				
		a) Trail	260	m ³	\$ _____	\$ _____
		b) Planting Beds and Tree Planting	440	m ³	\$ _____	\$ _____
		c) Armourstone seatwalls	2	m ³	\$ _____	\$ _____
		d) Armourstone retaining walls	2	m ³	\$ _____	\$ _____
		e) Asphalt Material (any thickness)	105	m2	\$ _____	\$ _____
B3	SPCS	Granular Material				
		a) Granular 'A'				
		i. Asphalt Walkway (150mm Depth)	430	t	\$ _____	\$ _____
		ii. Bench Pads (150mm Depth)	15	t	\$ _____	\$ _____
B9	SPCS	Concrete Sidewalks <i>32MPa Concrete</i>				
		a) Concrete Pads for Benches, Bike Racks, 125mm	30	m ²	\$ _____	\$ _____
B14	SPCS	Supply & Place Hot Mix Asphalt				
		a) HL3F 50mm thickness	180	t	\$ _____	\$ _____
B15	SPCS	Asphalt Walkways and Driveways <i>For Preparation & Handwork</i>				
		a) Asphalt Trail	1,300	m ²	\$ _____	\$ _____
B22	SPCS	Topsoil, Seed and Mulch <i>Includes any grading necessary to provide positive drainage</i>				
		a) 100mm Topsoil, Seed & Mulch (seed type 1)	1700	m ²	\$ _____	\$ _____